



NDCEE

National Defense Center for Energy and Environment

Zero Energy Homes for Military Installations

**E2S2 Conference
Denver, Colorado
May 6, 2009**

Ms. Heidi Anne Kaltenhauser, CTC/NDCEE



DoD Executive Agent

Office of the
Assistant Secretary
of the Army
(Installations and
Environment)

The NDCEE is operated by:  *Concurrent Technologies Corporation*

Technology Transition – Supporting DoD Readiness, Sustainability, and the Warfighter

Report Documentation Page				Form Approved OMB No. 0704-0188	
Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.					
1. REPORT DATE 06 MAY 2009		2. REPORT TYPE		3. DATES COVERED 00-00-2009 to 00-00-2009	
4. TITLE AND SUBTITLE Zero Energy Homes for Military Installations				5a. CONTRACT NUMBER	
				5b. GRANT NUMBER	
				5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NUMBER	
				5e. TASK NUMBER	
				5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) National Defense Center for Energy and Environment, Operated by Concurrent Technologies Corporation, 100 CTC Drive, Johnstown, PA, 15904				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)	
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution unlimited					
13. SUPPLEMENTARY NOTES Presented at the Environment, Energy & Sustainability Symposium & Exhibition (E2S2), 4-7 May 2009, Denver, CO.					
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT Same as Report (SAR)	18. NUMBER OF PAGES 27	19a. NAME OF RESPONSIBLE PERSON
a. REPORT unclassified	b. ABSTRACT unclassified	c. THIS PAGE unclassified			

Presentation Overview

- Project Objective And Drivers
- Project Evolution (Phase I and II)
- Project Team and Approach
- Design Approach
- Energy Modeling Results
- Path Forward

OBJECTIVE: Help the DoD build cost-effective, energy-efficient housing. As a step towards achieving this, the NDCEE is assisting with the design and evaluation of the performance of ZEH for military installations.

Project Drivers

- In FY06, 300,000 DoD homes used 11 trillion BTUs of electricity at a cost of \$254M
- Military Housing Privatization Initiative of 1996 provides opportunity for private expertise/capital to be used for military housing (DoD is privatizing 195,000 homes by 2010)
- Executive Order 13423, Energy Policy Act of 2005, and Army policy require more energy-efficient/less polluting buildings
- Energy efficiency leads to reduced electricity use and costs, increased energy security, supply stability, reduced greenhouse gases, and improved living environment
- Work is transferable across all Services and into the private sector

Project Overview

- Use integrated design and energy modeling to demonstrate zero energy housing
- Validate the potential to provide cost effective zero energy housing
- Transfer project knowledge DOD-wide and beyond

ESTCP Project Team

Stakeholders

Environmental Security Technology Certification Program (ESTCP)
US Army Installation Management Command Southeast (IMCOM SE)

Team Members

National Defense Center for Energy and Environment (NDCEE)
Fort Campbell
Fort Campbell Family Housing (FCFH)
Actus Lend Lease
Pacific Northwest National Laboratory (PNNL)
National Association of Home Builders Research Center (NAHB-RC)
7- Group
Lockett and Farley

Project Approach

- Design
 - Establish Approach and Methods
 - Delineate Constraints
 - Establish Baseline
 - Establish Initial Energy Efficiency Design
 - Model Charrette Technologies
 - Final Design
- Construction
- Monitoring
- Technology Transfer

Design Approach and Methods

- Held design team teleconferences to begin to:
 - identify constraints/baseline conditions
 - set performance goals
 - identify specific technologies, tools, and strategies.
- Held two-day design charrette with multi-disciple, multi-organizational team
- Tools used:
 - Integrated Design: Replaces the traditional sequential design process by integrating multiple disciplines early in the process to help identify and optimize systems and reduce overall costs
 - Energy modeling and analysis
 - Life-cycle cost analysis

Constraints

- Street exterior to be unaltered
- Baseline and ZEH to be placed in existing development plan
- Occupants historically not responsible for utilities
- Work within existing floor plan



Baseline Design

- Duplex
- Four-bedroom
- Two-story dwelling
- 1,985 square feet of conditioned space per unit
- 2.5 baths
- Energy Star Rating



Photo courtesy of Luckett & Farley; Architect of Record.

Pre-Charrette Recommendations

- Ground-source heat pumps
- High R-values: R25 walls, R49 ceiling, R30 over garage, R10 slab
- Energy Star appliances
- Hard-wired lighting 100% fluorescent
- Low air leakage, ventilation air heat recovery
- Solar water heater
- Other considerations:
 - More southern windows
 - Ceiling fans
 - Reduced misc. loads
 - Solar clothes dryers (clothes lines)

Design Charrette: August 25-26, 2008

- FCFH
 - Lockett and Farley Architects
 - Construction staff
 - Maintenance staff
 - Cost estimator
 - HVAC contractor
- ESTCP
 - NDCEE
 - 7 Group
 - PNNL
 - NAHB
 - IMCOM-SE



Major Design Element Changes: Envelope

- Insulation
 - 2x6 Walls – R19 + R5 sheathing
 - Floor over garage – R30
 - Attic – R60
- Sealing
 - Wall and cavity
 - Top plates
- Windows
 - Max U-value 0.31
 - Max SHGC 0.32

Major Design Element Changes: Hot Water (87% decrease)

- Centralized tank
- Manifold distribution
- Solar thermal preheat - 64-80 ft² collector
- 120 gallon storage tank with 4,500 W element

Major Design Element Changes: Appliances

- High efficiency
 - Clothes washer – 66% decrease
 - Dishwasher – 72% decrease
 - Exhaust fans
- No change
 - Clothes dryer
 - Range
 - Refrigerator


Major Design Element Changes: HVAC

- Ground Source Heat Pump
 - 18 EER and 4.0 COP
- Ducts
 - Sealed
 - Insulated

Modeled Demand Reductions

- Total Electric Demand 54%
 - Heating/Cooling/Hot Water 75%
 - Appliances and Lights 23%

Modeling Results



Design Lessons Learned

- Up front energy modeling beneficial to assess alternatives
- Iterative energy modeling during design is useful to assess effect of changes
- There's no substitute for having all parties engaged: designers, maintainers, constructors, vendors, users
- Occupant behavior has large and growing impact on success

Initial Exterior Design




Redesign of South facing roof provides space for solar water heating and photovoltaics

Replace gables and hip with shed; added porch roofs



Final Roof Design with PV Array

- 6 Strings of 11 panels in series
- 33 – 225 W panels per unit
- 7,425 W per unit
- 14,850 W total



Drawing Courtesy of Luckett and Farley

Cost Implications

- Early modeling
 - 7% increase in first costs for energy demand reduction
 - 25% increase in first costs for renewables
 - Payback 25-30 years
- 98% design snapshot
 - Still being evaluated

Measuring Success: Initial ZEH Performance Objectives

- Reduce design energy demand
 - 50% less than current duplex demand of 34.8 kbtu/sf
 - 60% less than national average demand of 46.7 kbtu/sf
- Reduce modeled net energy use of design to zero
- Reduce water consumption per capita by 30%
- Reduce measured energy consumption
 - Whole building – 50%
 - HVAC – 60%
 - Domestic hot water – 60%
 - Lighting – 10%
 - Plug loads – 10%
 - Appliances – 20%
- Reduce estimate air emissions, including CO₂
- Achieve measured energy generation @ 80% of design intent
- Maintenance – no cost/manpower increase
- Occupant satisfaction – higher for ZEH

Measuring Success: Occupants are the Key

- 3,337 kWh/year plug loads – 35% of remaining demand
- Our approach
 - Willing volunteers
 - Monitoring equipment in living space
 - Education program
 - Monthly feedback and support from research team
 - Occupant comfort surveys

Measuring Success: From Demonstration to SOP

- FCFH and Actus Lend Lease are considering using the following technologies in all new construction:
 - Ground source heat pumps
 - All compact fluorescent lighting
 - High efficiency appliances

Next Steps

- Construction and Monitoring
 - Includes occupant education program
 - Commissioning
- Performance Validation
 - Energy consumption, cost, and use patterns
 - Environmental impacts
 - On-site energy production
 - Maintenance costs and labor-hours
 - Occupant comfort and satisfaction
 - Lifecycle cost, net present value, simple payback

Final Steps

- Technology Transfer
 - Present results at energy and construction industry conferences
 - Produce case study
 - Develop ESTCP reports
 - Incorporate lessons learned into over 40,000 military housing units that Actus Lend Lease is building nationwide

Project Contacts

- Manette Messenger, IMCOM SE, 404-464-0786, manette.messenger@us.army.mil
- Heidi Anne Kaltenhauser, NDCEE/CTC, 502-425-1385, kaltenha@ctc.com

This work was funded through the Environmental Security Technology Certification Program (ESTCP) and conducted under contract W74V8H-04-D-0005 Task 0509. The views, opinions, and/or findings contained in this paper are those of the author and should not be construed as an official Department of the Army position, policy, or decision unless so designated by other official documentation.